



PERSPECTIVE VIEW

ERECTION NOTES:			
1	INDICATES MARKED END OF MEMBER.		
2	MEMBERS TO BE ERECTED WITH ASSEMBLY MARK AT THIS LOCATION.		
3	ORIENTATE COLUMN AS PER DIRECTION STAMPED AT BASE OF SHAFT.		
4	FIN PLATES FOR BEAMS WILL BE ON THE NORTH OR WEST SIDE OF BEAM		
5	WEB LIND. IF ERECT BEAMS TO SOUTH OR EAST SIDE OF FIN PLATES.		
6	FIN PLATES FOR CHANNELS ARE ON HEEL, OUTSIDE FACE OF WEB LIND.		
7	ALL DAMAGED OR WARE STEEL AREAS TO BE REPAIRED TO THE		
8	APPROPRIATE SURFACE TREATMENT AND PAINT SPECIFICATION.		
	ALL PURLING TO TIE UP ROOF LINE UNLESS NOTED "X" TIE DOWN.		



STRUCTURAL
STEEL DETAILING
ABN 44 160 875 758

CONTACT Clayton Andrews
MOBILE +61 (0)468 585 215
EMAIL c.andrews@warlin.com.au
www.warlin.com.au

Project : UQ Women's College New Centenary Wing			
Client :			
Drawn: CA	Checked: CA	Date: 13.09.2014	Scale: 1:100

Description CW - PERSPECTIVE VIEW1	Job No. WC_0066
Drawing No. MP100	Rev 0

0	ISSUED FOR FABRICATION	17.09.2014	CA
A	ISSUED FOR APPROVAL	14.09.2014	CA
Rev	Revision Details	Date	Drawn